


HYER STANDARDS

Wet Areas


The Hansen Yuncken HYer Standards provide guidance on the minimum level of compliance expected for high risk activities on all projects.

Substrate and Preparation




- Wall framing/structure is to be checked and accepted, with noggins for fixings in place prior to installation of wall linings.
- Bond breakers and penetration collars/safe wastes correctly installed prior to application of waterproofing membrane.
- Waterproofing membrane is to be free of damage prior to installation of substrate.
- Substrate to be accepted prior to application of finishes. Falls to floor waste to be per specified requirements.
- Wall render/linings to be checked for flatness
- Caulking of tapware spindles, wall pipework penetrations to be completed in accordance with manufacturer’s recommendations.

Installation




- Tiling adhesive is to cover >90% per tile unit and allowed to set for a minimum of 12 hours prior to grout application
- Grout/Joint alignment is to be within acceptable tolerances
- Vinyl joints are to be neat and of consistent width/thickness
- Plumbing penetrations/fixtures are to be sealed with approved flexible sealant- membrane integrity maintained.
- Drainage outlets function has been checked and are free of blockage/s.
- Finished surfaces cleaned upon completion.
- Completed areas have been appropriately protected.

Approvals

COLOUR	Unite White Gloss 2(00x400)	
OTHER		
		
SAMPLE CHECKLIST	TECHNICAL CERTIFICATES (AND TECH DATA)	<input type="checkbox"/>
	PHYSICAL SAMPLES	<input checked="" type="checkbox"/>

- Approvals for materials and samples are to be in accordance with the project’s specifications
- Subcontractors ITP must be reviewed and approved by Hansen Yuncken.
- Supporting documentation, submissions, certifications, and test reports are to be per current Project Specifications.

Hold/Witness Points



- Wall framing/structure accepted by HY prior to sheeting
- Waterproofing membrane application inspected by HY prior to any testing
- Waterproofed areas inspected and tested by subcontractor
- All Substrate/ preparation works completed and fixtures installed prior to tiling/vinyl/glazing installation